


DuraWeld Pro Gabion Fence







Made of electro-spot-welded, steel-wire mesh grids with easy to assemble end panels, the DuraWeld Pro Gabion Fence System is an excellent choice when aesthetics and safety are paramount. With high quality manufacturing from Germany, we are able to offer a superior gabion fence solution to the North American market.

- Premium Quality and Aesthetics
- Minimal Seams
- Easy to Extend
- Easy to Assemble
- Precise Dimensions
- Rectangular Mesh Openings

Applications:


- · Garden/Landscape Design
- Installations close to pedestrians (nursery and public schools, retirements homes, residential areas, playgrounds, parking lots)
- Privacy Fences
- Boundary Lines
- Anti-Noise Barriers


Technical Specifications:

- Electro-Spot-Welded Steel Wire
- Zinc-Aluminum Coating (95% zn / 5% al)
- 2.5x10 cm / 1x4 in Mesh Size
- 3.5 mm / 0.14 in Mesh Vertical Wire Diameter
- 5 mm / 0.2 in Mesh Horizontal Wire Diameter
- Tensile Strength Min. 450 N/mm²
- Min. 3,000 hr salt spray testing in accordance with DIN EN ISO 9227-NSS
- Additional mesh dimensions available with production lead-time (5x10cm and 5x20cm)

Benefits:

- DURABLE Corrosion resistant thanks to ZnAl coating
- EASY TO ASSEMBLE Mesh panels easily connect with hook-in end panels
- DIMENSIONALLY STABLE Each module uses two support posts and panels lock from weight of fill material
- AESTHETICALLY PLEASING Rectangular mesh openings and customizable fill options





Rock-Fill:

Gabions should be filled with hard and durable material that is frost, weather and pressure resistant.

Stone sizing should be larger than the mesh opening size, especially at the face of the basket.

Basic Module

A Basic Module consists of a complete set including 2 facing panels, 2 side/end panels and a cover panel. Extension Module includes everything above except the 2 side/end panels. Panels for the bottom of the gabions are not included in the standard fence module.

Shortening and cutting of fence modules is possible by cutting mesh panels at outside of welded junction.

Many module sizes are stock items but confirm inventory levels based on the size of your project and desired dimensions. Lead time for additional modules not in stock should be 6-8 weeks

Modules can be stacked on top of each other by securing the lower and upper facing panels to each other with hog rings or tie wire.

DuraWeld Pro Gabion Fence Module Dimensions			
Length	Width	Height	
100 cm / 39.4 in	23 cm / 9.06 in	100 cm / 39.4 in	160 cm / 62.99 in
200 cm / 78.74 in	30 cm / 11.81 in	120 cm / 47.24 in	180 cm / 70.87 in
		140 cm / 55.12 in	200 cm / 78.74 in